

B

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -077- 20469-00-00 (of this well)

Operator's Full Name Texas Oil & Gas. Corp.  
Complete Address Suite 300, 200 W. Douglas, Wichita, KS 67202  
Lease Name Stevens Well No. C-1  
Location N/2 - NW - Sec. 3 Twp 31 Rge. 7 (E) (W) X  
County Harper Total Depth 4800  
Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A         
Other well as hereafter indicated       

Plugging Contractor Clarke Corp.  
Address 107 W. Fowler, Medicine Lodge, KS 67104 License No. 583  
Operation Completed: Hour 10:30 Am Day 27 Month March Year 1978

The above well was plugged as follows:

250' - 8 5/8" Casing - Cont. Circ. - 4 1/2" Casing set @ 4440 w/150  
saf Cement - plug back to 4355' - pref. 4300' to 4338'  
squeeze w/150 saf Cement - Sand back to 4250' - mix & dump  
w/ dump bailer & saf Cement on top of sand - Pull 3600'  
4 1/2" Casing - set bridge from 280' back to 260' - dump  
4 1/2 yard Cement to top of Casing -  
Harper Ready Mix - Harper, KS - 67058

RECEIVED  
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED

MAR 29 1978  
03-29-1978  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: [Signature]  
Well Plugging Supervisor

DATE 3-30-78  
INV. NO. 7012-W