

15-165-20469-0000

[Signature]
KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

MAR 27 1975
3-27-75
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Al Tipton

Complete Address Box 157, Hays, Kansas 67601

Lease Name S. Miller Well No. 1

Location C NW NE Sec. 13 Twp. 19 Rge. (E) (W) 16

County Rush Total Depth 3721'

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling

Address Box 405, Chase, Kansas 67524 License No. 436

Operation Completed: Hour 2 P Day 24 Month 3 Year 1975

The above well was plugged as follows:

Total Depth 3721' 8 5/8 csg set 1037' cwc 400 sk.

4 1/2 csg 3720' W/100 sk cem.

4 1/2 csg PBSD 3681' with top perf. (3652')

Filled 4 1/2 csg with snd (3681-3600) dumped 5 sk cem. W/dump bailer. (3600-3565)

Cutoff & recovered A/2900' of 4 1/2 csg.

Drlg. mud to 360' -rock & sand bridge (360-350)

Filled with readymix cem. from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Warner
Well Plugging Supervisor

DATE 4/1/75
INV. NO. 1093-W