

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

FEB 12 1974  
2-12-74  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Alvin E. Tipton Oil Properties

Complete Address P. O. Box 175 Hays, Kansas 67601

Lease Name Grunwald Well No. 1

Location NE NE SW Sec. 13 Twp. 19 Rge. (E) (W) 16

County Rush Total Depth 3724'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 10 A Day 9 Month 2 Year 1974

The above well was plugged as follows:

Total Depth 3724' 8 5/8 csg set at 1040' cwc

5 1/2 csg set at 3724' cw 100 sk cmt.

5 1/2 csg PBD 3705' with top perf. (3647)

5 1/2 csg squeezed at 2576' W/100 sx cem.

Filled 5 1/2 csg W/sd (3605-3600) dumped 5 sk cmt W/dump bailer. (3600-3565)\*

Cutoff and recovered 2100' of 5 1/2 csg.

Filled 5 1/2 csg with mud to 300' -set reek & reek bridge (300-285)

Filled with readymix cement from 285' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 2/12/74

ENV. NO. 8559-W