

2

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
CORPORATION COMMISSION
NOV 14 1977
11-14-77
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -165-30102-00-01 (of this well)

Operator's Full Name J. C. Musgrove, Inc.

Complete Address Box 611, Great Bend, Kansas 67530

Lease Name Damm Well No. 1

Location C SE NW Sec. 12 Twp. 19 Rge. (E) (W) 16

County Rush Total Depth 3646'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698, Great Bend, Kansas License No. 670

Operation Completed: Hour 5:30 P Day 11 Month 11 Year 1977

The above well was plugged as follows:

Total Depth 3646' 8 5/8 csg set 1039' cwc 420 sk.

4 1/2" csg set 3645' cw 100 sk cem. Top perf. (3608')

Filled 4 1/2" csg with sand (3646'-3590') dumped 4 sk cem W/dump bailer. (3590'@3570')

Cutoff & recovered A/2800' of 4 1/2" csg.

Drilling mud to 425' -set rock & sand bridge (425'-415')

Filled with readymix cem from 420' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Les Massey
Well Plugging Supervisor

DATE 11-14-77
INV. NO. 6193-W