

P

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-165-20570-0000 (of this well)

Operator's Full Name Roxana Corporation

Complete Address Box 611, Great Bend, Ks. 67530

Lease Name Miller "A" Well No. 1

Location C NE SE Sec. 12 Twp. 19 Rge. (E) (W) 16

County Rush Total Depth 3636'

Abandoned Oil Well X Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering

Address Box 698, Great Bend, Ks. 67530 License No. 670

Operation Completed: Hour 2:20 P Day 21 Month 4 Year 1979

The above well was plugged as follows:

TD 3636' 8 5/8 csg set 1010' cwc 375 sk.

5 1/2 csg set 3635' cw 150 sk cem.

5 1/2 csg PBDT 3610' with top perf. (3596')

Filled 5 1/2 csg W/sd (3610'-3575') dumped 5 sk cem W/dump bailer. (3575'-3545')

Cutoff & recovered A/2000' of 5 1/2 csg.

Drilling mud TD-300'. Set rock & sand bridge & filled with readymix cem. (300' to base of cellar.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4-24-79
INV. NO. 9488-W

Signed: [Signature]
Well Plugging Supervisor

RECEIVED
STATE CORPORATION COMMISSION
APR 23 1979
4-23-79
CONSERVATION DIVISION
Wichita, Kansas