

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 15 1977
2-15-77

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 20586 - 0000 (for this well)

Operator's Full Name Okmar Oil Company

Complete Address 970 Fourth Financial Center, Wichita, Kansas 67202

Lease Name Bagsinger Well No. 1

Location SW NW SW Sec. 5 Twp. 16 Rge. (E) (W) 26

County Ness Total Depth 4536'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 2:30 P Day 10 Month 2 Year 1977

The above well was plugged as follows:

Total Depth 4536' 8 5/8 csg set 296' cwc 225 sx.

4 1/2 cag set 4535' cw 150 sx.

4 1/2 csg PBSD 4466' with PFS (4401'-4406')

Filled 4 1/2 csg W/sd (4466'-4350') dumped 4 sx cem W/dump bailer. (4350'-4300')

Cutoff & recovered 2913' of 4 1/2 csg.

Sun Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water- followed

with 70 sk 50-50 poz cem. 6% gel -displaced with 10 sk gel & water -released

8 5/8 plug & capped with 50 sk 50-50 poz 6% gel & shutin. MPP 500 lbs SIP 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 2-15-77

INV. NO. 464-W