

KANSAS

Form **CP-31** RECEIVED
STATE CORPORATION COMMISSION
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

DEC - 8 1978
12-8-78
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21,480-1800 (of this well)

Operator's Full Name Twin Western Resources, Inc.

Complete Address 920 Union Center Bldg., Wichita, Kansas

Lease Name Peters Well No. 1

Location C N/2 NW NW Sec. 15 Twp. 16 Rge. (E) (W) 26

County Ness Total Depth 4555'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Warrior Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 1 P Day 7 Month 12 Year 1978

The above well was plugged as follows:

RTD 4555' 8 5/8 csg set 291' cwc 200 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 800' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12-11-78

INV. NO. 8711-W

Signed: Leo Massey
Well Plugging Supervisor