

15/35-20897-0000

Form CP-3
Rev. 6-4-68



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1974
6-20-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Dane G. Hansen Trust
Complete Address Box 187 Logan, Kansas 67646
Lease Name Holmes "A" Well No. 1
Location NW NE SW Sec. 15 Twp. 16 Rge. (E) (W) 26
County Ness Total Depth 4564'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor C & G Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 9 A Day 17 Month 6 Year 1974

The above well was plugged as follows:

RTD 4564' 8 5/8 csg set at 200' cwc 150 sk. Cem. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 185' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo G. Massey
Well Plugging Supervisor

INVOICED

DATE 6/24/74
INV. NO. 9361-W