

KANSAS

STATE CORPORATION COMMISSION

R

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
10-12-76
OCT 12 1976
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 21,254-000 (of this well)

Operator's Full Name Abercrombie Drilling, Inc.

Complete Address 801 Union Center, Wichita, Kansas

Lease Name Jarvis Well No. 1

Location NW NW NE Sec. 10 Twp. 16 Rge. (E) (W) 26

County Ness Total Depth 4575'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 9:30 P Day 9 Month 10 Year 1976

The above well was plugged as follows:

RTD 4575' 8 5/8 csg set 380' cwc 225 sx. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 800' thru drill pipe. ~~XXXXXXXXXXXX~~

Heavy mud to 300' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 10-12-76

INV. NO. 3976-W