

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 10 1973  
12-10-73  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Patrick Petroleum Corp.  
Complete Address Suite 330 Page Court, 220 W. Douglas Wichita, Kansas  
Lease Name Jarvis Well No. 1  
Location SW SE NE Sec. 10 Twp. 16 Rge. (E) (W) 26  
County Ness Total Depth 4604'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Slawson Drlg.  
Address Wichita, Ks. License No.         
Operation Completed: Hour 9:15 A Day 4 Month 12 Year 1973

The above well was plugged as follows:

RTD 4604' 8 5/8 csg set at 309' cwe Cmt. Mat. 50-50 poz W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED  
DATE 12/10/73  
INV. NO. 8275-W