

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-135 - 20,810-0000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name PETROLEUM, INC.

Complete Address Box 1447, GREAT BEND, KS 67530

Lease Name PETERS "D" Well No. # 2

Location C. SW Sec. 10 Twp. 16 Rge. 26 (East) (West)

County NESS Total Depth 4578'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor BARLOW WELL SERVICE

Address \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour: 7:40 pm Day: 19 Month: 7 Year: 1982

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 7/8 sp. @ 319' w/225 sx  
5 1/2" @ 4577' w/100 sx; REC/2616'  
P.B.T.D. 4535'; PERF. 4023'  
Bridge Plug @ 4000' w/25 sx CMT  
Plugged as follows: 3 hulls - 15 gel - 70 cmt - 1 hull -  
15 gel - rel. 8 5/8" plug - 80 cmt  
Cement used: 50-50 poz mix w/ 7% gel - 3% CC  
Max press: 400# shut in 100#  
Amount of Surface Casing: 319'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Steve Lument  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Working in Judge's office

RECEIVED  
AUG 02 1982  
8-2-82  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: S. Lument  
Conservation Division Agent

INVOICED

DATE 8-11-82

INV. NO. 885-w