

R

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 20793-0000 (of this well)

7-19-77
JUL 20 1977

Operator's Full Name Patrick Petroleum Corporation

Complete Address 200 East First, Suite 414, Wichita, Kansas 67202

Lease Name Baker Well No. 1

Location NE SE SE Sec. 10 Twp. 16 Rge. (E) (W) 26

County Ness Total Depth 4537'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 11:30 P Day 15 Month 7 Year 1977

The above well was plugged as follows:

Total Depth 4537' 8 5/8 csg set 277' cwc 170 sk.

5 1/2 csg set 4534' cw 150 sk cem.

Filled 5 1/2 csg W/sd (4537'-4500') dumped 4 sk cem W/dump bailer. (4500'-4470')

Cutoff & recovered 2015' of 5 1/2 csg.

Halliburton Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water

W/100 lbs hulls -followed with 70 sk 50-50 poz 6% gel -displaced with 12 sk

gel & water capped with cementing plug & 70 sk 50-50 poz 6% gel & shutin.

FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 7-19-77

INV. NO. 55164