

15.135.30135.0000


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ness County. Sec. 7 Twp. 16 Rge. 26 XXXXXXX(W)

Location as "NE/CNW/SW" or footage from lines NE SW
Lease Owner Empire Drilling Company
Lease Name Armstrong Well No. 3
Office Address 650 4th Natl. Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 11 19 65
Application for plugging filed December 11 19 65
Application for plugging approved December 11 19 65
Plugging commenced December 11 19 65
Plugging completed December 11 19 65
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker, 805 Main, Victoria, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4569 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|--------------|------|-----|---------|--------|------------|
| Surface | Sand - Shale | 0 | 133 | 10 3/4" | 116' | -0- |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set at 540' with 20 sacks cement.
Plug set at 100' with 25 sacks cement.
Plug set at 40' with 20 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1965
12-23-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company
Address 650 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dan J. Kornfeld

(~~employee or operator~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld
650 4th Natl. Bank Bldg., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of December, 19 65

My commission expires September 14, 1968.

Sandra Kay Peer
Sandra Kay Peer
Notary Public.

LOG

15-135-30135-0000

COMPANY: Empire Drilling Company
CONTRACTOR: Empire Drilling Company
FARM: Armstrong #3
LOCATION: NE SW Section 7-16S-26W, Ness County, Kansas

COMMENCED: November 30, 1965 ELEVATION: 2662 KB
COMPLETED: December 11, 1965 POTENTIAL: D & A

| | | | |
|------|----|------|--------------------------|
| 0 | to | 133 | Surface - Sand - Shale |
| 133 | to | 1575 | Shale |
| 1575 | to | 2055 | Shale & Sand |
| 2055 | to | 2057 | Redbed |
| 2057 | to | 2096 | Anhydrite |
| 2096 | to | 2230 | Shale & Shells |
| 2230 | to | 2530 | Shale - Salt |
| 2530 | to | 2870 | Shale & Lime |
| 2870 | to | 3275 | Lime |
| 3275 | to | 3625 | Lime & Shale |
| 3625 | to | 3923 | Lime |
| 3923 | to | 4245 | Lime & Chert |
| 4245 | to | 4490 | Lime & Shale |
| 4490 | to | 4538 | Lime & Chert |
| 4538 | to | 4560 | Mississippi Lime & Chert |
| 4560 | to | 4568 | Mississippi |
| 4568 | | | Rotary Total Depth |

SET: 116' of 10 3/4" with 60 sacks cement.

SCHLUMBERGER ELECTRIC LOG TOPS:

| | | |
|----------------------|------|-------|
| Anhydrite | 2055 | +607 |
| Waubensee | 3491 | -829 |
| Topeka | 3680 | -1018 |
| Queen Hill | 3765 | -1103 |
| Heebner | 3898 | -1236 |
| Toronto | 3917 | -1255 |
| Lansing | 3935 | -1273 |
| Muncie Creek | 4088 | -1426 |
| Base Kansas City | 4243 | -1581 |
| Pawnee | 4330 | -1668 |
| Fort Scott | 4387 | -1725 |
| Cherokee Group | 4437 | -1775 |
| Conglomerate | 4521 | -1859 |
| Reworked Mississippi | 4533 | -1871 |
| Mississippi Lime | 4548 | -1886 |
| Mississippi Dolomite | 4558 | -1896 |
| Log Total Depth | 4569 | |

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1965

CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Armstrong #3, NE SW Section 7-16S-26W, Ness County, Kansas, as reflected by the files of Empire Drilling Company.

Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 17th day of December, 1965.

Sandra Kay Peer, Notary Public

My commission expires September 14, 1968.