


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 6 Twp. 16S Rge. 26 NE/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines _____
C E/2 SE SW
Lease Owner Blue Goose Drilling Company, Inc. # 5104
Lease Name Carlson Well No. 2
Office Address PO Box 1413 Great Bend, KS 67530
Character of Well (Completed as Oil, Gas or Dry Hole) _____
DRY HOLE
Date Well completed 7-28- 19 84
Application for plugging filed 7-27- 19 84
Application for plugging approved 7-27- 19 84
Plugging commenced 7-27- 19 84
Plugging completed 7-28- 19 84
Reason for abandonment of well or producing formation _____
Dry Hole
If a producing well is abandoned, date of last production _____
19 _____



Locate well correctly on above
Section Plat

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4570'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	383'	8 5/8	381	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

4570' T.D. 170 Sacks 60-40 Posmix 3% cc 2% Gel
1st plug @ 2100' with 50 Sacks
2nd plug @ 1140' with 50 Sacks
3rd plug @ 420' with 50 sacks
Solid Bridge @ 40' (Sack Hulls) with 10 sacks
Rathole 10 sacks
Plug down 12:15 A.M. 7-28-84
Sun Cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Blue Goose Drilling Company, Inc. # 5104

STATE OF KANSAS COUNTY OF BARTON, ss.
George E. Miller, Jr. (~~employee of owner~~) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) George E. Miller, Jr.
Box 1413 Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of July, 19 84

Helen C. Standley
Notary Public.

My commission expires 12-8-87

RECEIVED
STATE CORPORATION COMMISSION
HELEN C. STANDLEY
Barton County, Kansas
My Appt. Exp. 12-8-87

AUG 08 1984
8-8-84
CONSERVATION DIVISION
Wichita, Kansas