


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Ness County. Sec. 5 Twp. 16 Rge. 26 E/W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines  
SW ~~NW~~ SW  
Lease Owner Okmar Oil Company  
Lease Name Basinger #1 Well No. \_\_\_\_\_  
Office Address Hays, Kansas 67601  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above  
Section Plat

Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 2/1/77 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 2/10/77 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation  
depleted. \_\_\_\_\_  
If a producing well is abandoned, date of last production  
\_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4536  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8  | 296    | none       |
|           |         |      |    | 4 1/2" | 4535   | 2915       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pushed wood plug to 4350', sanded to 4300' and ran 4 sacks cement.  
Loaded hole with salt water, shot pipe at 3516', spotted oil, used  
50 bbls. oil. Shot pipe at 3313', 3114', 2913',  
pulled 60 joints. Pumped 20 sacks gel, 70 sacks cement, 10 sacks  
gel, released plug and ran 50 sacks cement.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
2-22-77  
FEB 22 1977

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of Feb., 1977

My commission expires \_\_\_\_\_



Margaret Melcher  
Notary Public.

DRILLERS LOG

#1 Bassinger

15135-20986-0000

CASING: 296.74' of used 8-5/8" surface casing.

COMPANY: Okmar Oil Company

DESCRIPTION: SW NW SW Section 5-16S-26W Ness County, Kansas

CONTRACTOR: Strata Drilling Company

TOTAL DEPTH: 4536'

COMMENCED: April 1, 1975

COMPLETED: April 15, 1975

| <u>FORMATION</u>     | <u>FROM</u> | <u>TO</u> | <u>REMARKS</u>   |
|----------------------|-------------|-----------|--|
| Surface Soil & Shale | 0           | 220       | Ran 296.74' of used 8-5/8" surface casing; set and cemented at 302.24' with 120 sacks of 50/50 pozmix and 6% gel and 175 sacks of 60/40 pozmix, 3% gel and 3% C. C. Plug down at 3:00 A. M. April 2, 1975. |
| Shale                | 220         | 615       |  |
| Shale w/Sand Streaks | 615         | 1215      |  |
| Shale                | 1215        | 1467      |  |
| Anhydrite            | 1467        | 1477      |  |
| Shale & Red Bed      | 1477        | 1575      |  |
| Sand                 | 1575        | 1800      |  |
| Red Bed & Shale      | 1800        | 1905      |  |
| Shale                | 1905        | 2163      |  |
| Shale & Lime         | 2163        | 3140      |  |
| Lime                 | 3140        | 3520      |  |
| Lime & Shale         | 3520        | 3675      |  |
| Lime                 | 3675        | 3790      |  |
| Lime & Shale         | 3790        | 4080      |  |
| Lime                 | 4080        | 4135      |  |
| Lime & Shale         | 4135        | 4432      |  |
| Lime                 | 4432        | 4450      | Ran Drill Stem Tests.<br>Ran Electric Log.   |
| Lime & Shale         | 4450        | 4536      |  |

ROTARY TOTAL DEPTH: 4536' RECEIVED STATE CORPORATION COMMISSION

JAN 05 1977

CONSERVATION DIVISION  
Wichita, Kansas

Ran 93 joints of new 4 1/2" casing; set and cemented at 4535' with 75 sacks of 60-40 pozmix, 18% salt saturated. Plug down at 6:45 A. M. April 15, 1975.

STATE OF KANSAS )  
COUNTY OF BARTON ) ss.

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

*Kenneth J. Link*  
Kenneth J. Link, President

Subscribed and sworn to before me this 22nd day of April, 1975.

My Commission Expires:

December 14, 1977  
ELAINE H. TAYLOR  
NOTARY PUBLIC  
BARTON COUNTY, KANSAS

*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public