

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Ness County. Sec. 15 Twp. 16S Rge. (E)26 (W)
Location as "NE/CNWxSWx" or footage from lines C N/2 NW NW
Lease Owner Twin Western Resources, Inc.
Lease Name Peters Well No. #1
Office Address Suite 920 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Dec. 7, 1978 19
Application for plugging filed Dec. 7, 1978 19
Application for plugging approved Dec. 7, 1978 19
Plugging commenced Dec. 7, 1978 19
Plugging completed Dec. 7, 1978 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4555' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	284'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged through drill pipe @ 800' w/70 sx. cement
Plugged through drill pipe @ 240' w/20 sx. cement
Plugged through drill pipe @ 40' w/10 sx. cement

DEC 27 1978
12-27-78

Name of Plugging Contractor Warrior Drilling, Inc.
Address 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Jim Robinson (employen of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
905 Century Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of December, 1978

My commission expires _____

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard
Marilyn Sinard
Notary Public.

Operator
TWIN WESTERN RESOURCES, INC.

DESIGNATE TYPE OF COMP.: OIL, GAS,
 DRY HOLE, SWDW, ETC.:
DRY HOLE

Well No. #1 Lease Name **Peters**

S. 15 T. 16 R. 26 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Anhydrite	2055			
Base-Anhydrite	2090			
Heebner	3903			
Lansing	3945			
Stark Shale	4186			
Base-Kansas City	4242			
Marmaton	4306			
Pawnee	4386			
Fort Scott	4450			
Cherokee	4476			
Conglomerate	4524			
Mississippian	4544			
Log total depth	4552			
Rotary Total depth	4555			
<p>DST #1 4102 - 4156' 30-60-30-60 Recovered 130' watery mud, IFP 67-54 FFP 92-82, IBHP 1297, FBHP 1297</p> <p>DST #2 4543 - 4555' 30-60-30-60 Recovered 110' muddy water IFP 23-14, FFP 48-26, IBHP 91, FBHP 89</p>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Stephen D. Wade
 Signature
Staff Geologist
 Title
12-27-78
 Date

DRILLERS LOG

December 12, 1978

#1 Peters
C N/2 NW NW Sec. 15-16S-26W
Ness County, Kansas

OPERATOR: Twin Western Resources, Inc.
CONTRACTOR: Warrior Drilling, Inc.
DATE SPUDDED: November 28, 1978
DATE COMPLETED: December 7, 1978
CASING RECORD: 8 5/8" @ 284' w/185 sx.

0	291	Surface Sand
291	1380	Sand & Shale
1380	1713	Shale & Sand
1713	2613	Sand & Shale
2613	3019	Shale
3019	3247	Lime
3247	3576	Shale & Lime
3576	3976	Lime
3976	4134	Shale & Lime
4134	4555	Lime
4555		Total Depth

RECEIVED
STATE CORPORATION COMMISSION


DEC 27 1978

CONSERVATION DIVISION
Wichita, Kansas


D & A

We certify that the above is a true and correct copy of the drillers log on the #1 Peters located in Ness County, Kansas.

WARRIOR DRILLING, INC.


Jim Robinson, Vice President

Subscribed and sworn to before me this 12th day of December, 1978.


Marilyn Sinard Notary Public