

LEASE NAME Furman

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

1980 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 12 TWP. 16S RGE. 26 ~~26E~~ or (W)

COUNTY Ness

Date Well Completed 1/15/97

Plugging Commenced 5:00PM 1/15/97

Plugging Completed 8:00PM 1/15/97

LEASE OPERATOR Dennis Kindsvater

ADDRESS P.O. Box 906 Dodge City, Kansas 67801

PHONE# (316) 227-2841 OPERATORS LICENSE NO. 31552

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/15/97 (date)

by Bill Johnson (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? No Log

Producing Formation None Depth to Top \_\_\_\_\_ Bottom 4478

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED  
KANSAS CORP COM  
1997 FEB 18 PM 3:30  
2-18-97

Formation	Content	From	To	Size	Put In	Pulled Out
		0	268	8 5/8	268	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to \_\_\_\_\_ feet each see

1st Plug @ 2060' w/50sks 10sks In Mouse Hole Circulated 1st Plug 15 Minutes w/50Vis. Mud

2nd Plug @ 1030' w/50sks 15sks In Rat Hole Plugs displaced with mud

3rd Plug @ 300' w/50sks Total 185sks 60/40Poz 6%Gel w/1#PS/sk By Halliburton

4th Plug @ 40' w/10sks Completed @ 8:00PM 1/15/97

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Discovery Drilling, Inc. License No. 31548

Address P.O. Box 763 Hays, Kansas 67601


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Dennis Kindsvater

STATE OF Kansas COUNTY OF ELLIS, ss.

RON NELSON (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed therewith are true and correct, so help me God.

(Signature) Ron Nelson

(Address) 3322 Lincoln Hays ks 67601



SUBSCRIBED AND SWORN TO before me this 14 day of Feb, 19 97

[Signature]  
Notary Public

My Commission Expires: 1-10-99