

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Scott T. Lutz

ADDRESS P.O. Drawer D Shell Knob, MO 65747

PHONE# (501) 443-5430 OPERATORS LICENSE NO. 7200

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 7/16/96

Plugging Commenced 6:30AM 7/16/96

Plugging Completed 9:15AM 7/16/96

The plugging proposal was approved on 7/15/96 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? No Log

Producing Formation None Depth to Top _____ Bottom T.D. 4547'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	271	8 5/8	271.49	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from _____ feet to _____ feet each s
1st Plug @ 2040' w/50sks 10sks In Mouse Hole Circulated 1st Plug 15 Minutes w/ 48 Vis. Mud
2nd Plug @ 1250' w/80sks 15sks In Rat Hole Plugs displaced with mud
3rd Plug @ 300' w/40sks Total 205sks 60/40Poz 6%Gel w/1#FS/sk By Allied Cementing
4th Plug @ 40' w/10sks Completed @ 9:15AM 7/16/96

RECEIVED
KANSAS CORPORATION COMMISSION
License No. 31548

Name of Plugging Contractor Discovery Drilling, Inc.

Address P.O. Box 763 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Scott T. Lutz

STATE OF _____ COUNTY OF _____

AUG 12 1996
8-12-96
CONSERVATION DIVISION
WICHITA, KS

(Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fac statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.

(Signature) Scott T. Lutz

(Address) _____

SUBSCRIBED AND SWORN TO before me this 8th day of August, 19 96

RECEIVED
KANSAS CORPORATION COMMISSION
James Roberts
Notary Public

My Commission Expires: March 31, 2000

USE ONLY ONE SIDE OF EACH FORM

AUG 05 1996