


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

*corp. common*

WELL PLUGGING RECORD



Harper County, Sec. 24 Twp. 31 Rge. (E) 7(W)

Location as "NE/CNW/SW" or footage from lines C NE NE

Lease Owner Phillips Petroleum Company

Lease Name Eisler Well No. M1

Office Address Box 287, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Miscellaneous - holding for future SWD

Date well completed Feb 11, 1964 19

Application for plugging filed 5-5-64 19

Application for plugging approved 5-6-64 19

Plugging commenced 5-18-64 19

Plugging completed 5-20-64 19

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. Elving, Box 248, Pratt, Kan.

Producing formation - Depth to top - Bottom - Total Depth of Well 4240 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	dry	3172		8-5/8	246'	none
KC	dry	3718		5 1/2	4400'	4205'
Miss	dry	4272				
Kinderhook Shale	dry	4542				
Simpson Sand	dry	4666				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded hole to 255', 10' rock bridge 255' to 245', 25 sx cement to 190', mudded hole to 40', 10' rock bridge to 30', 10 sx cement to surface. Job complete 1 p.m. 5-20-64 FINAL REPORT.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 25 1964

05-25-1964  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Csg Pulling Unit

Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

M. E. Michael ~~Area Supt~~ (employee of owner) or (~~agent~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. E. Michael

(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of May, 19 64

My commission expires 11-18-65

Joseph M. Beal  
Notary Public.



# WELL LOG 15-D77-19024-00-00

COMPANY Phillips Petroleum Company

SEC. 24 T. 31S. 7W

FARM Eisler NO. 1


LOC. NE NE

TOTAL DEPTH 4693'

COUNTY Harper

COMM. 1-10-64 COMP. 1-26-64

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 246' w/125 sx

5 1/2" @ 4406' w/65 sx

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 160' Red Rock
- 550' Red Bed and Shale
- 1230' Shale and Lime
- 1400' Shale
- 1835' Lime
- 2210' Lime and Shale
- 2465' Shale and Lime Streaks
- 2840' Shale and Lime
- 3322' Lime and Shale
- 3500' Lime
- 3738' Lime and Shale
- 3947' Lime
- 4270' Lime and Shale
- 4310' Shale and Lime
- 4550' Lime
- 4576' Lime and Shale
- 4628' Kinderhook
- 4672' Shale
- 4693' Simpson
- 4693' RTD

RECEIVED  
STATE CORPORATION COMMISSION

MAY 25 1964

CONSERVATION DIVISION  
Wichita, Kansas

05-25-1964

State of Kansas }  
County of Barton } SS

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Eisler #1 well.

Subscribed and sworn to before me this 31st day of January 1964

My Commission Expires: September 23rd, 1967

  
NOTARY PUBLIC