


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-077-20062-00-00 Form CP-4  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Harper County. Sec. 23 Twp. 31S Rge. (E) 7 (W)



Location as "NE/CNW/SW" or footage from lines C NW SE  
Lease Owner Anadarko Production Company  
Lease Name Parsons "F" Well No. 1  
Office Address Box 351 Liberal, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 6/17 19 68  
Application for plugging filed 6/16 19 68  
Application for plugging approved 6/16 19 68  
Plugging commenced 6/17 19 68  
Plugging completed 6/17 19 68  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren, Pratt, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4859 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	637'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.  
Spotted 45 sacks of cement from 2550 - 2400'.  
Pulled drill pipe to 300'. Circulated hole with mud.  
Spotted 35 sacks of cement @ 300'.  
Finished laying down drill pipe. Filled hole with mud to 40'.  
Spotted 15 sacks of cement from 40' to 0'.  
Plugged rat hole with 5 sacks of cement.  
Completed @ 8:15 A.M. 6/17/68.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 25 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
06-25-1968

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Leben Drilling, Inc  
Address 815 Wichita Plaza Building, Wichita, Kansas 67202


STATE OF Kansas, COUNTY OF Seward, ss.  
V. K. Downey (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

V. K. Downey, Superintendent (Signature) [Signature]  
Liberal Production Region Box 351 Liberal, Kansas 67901  
(Address)

Subscribed and sworn to before me this 21st day of June 1968

My Commission Expires May 11, 1971  
Keith S. Thomas Notary Public.



Keith S. Thomas

15-077-20062-00-00

DRILLER'S LOG

WELL NAME: Parsons "F" No. 1 ; COMPANY OPERATING: Anadarko Production Company  
 ADDRESS of COMPANY: Box 351 Liberal, Kansas 67901  
 WELL LOCATION: C  $\frac{1}{4}$  NW  $\frac{1}{4}$  SE  $\frac{1}{4}$ ,  
1980 ft. North of South line,  
3300 ft. East of West line: Sec. 23, Twp. 31S, Rge. 7W, Harper County, Kansas  
 DRILLING STARTED 6/3, 1968; DRILLING COMPLETED 6/17, 1968  
 WELL COMPLETED         , 19        ; WELL CONNECTED         , 19          
 ELEVATION: 1514.4 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Dry Hole

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 25 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8-5/8"	637'	450	None

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Surface Sand	0	30	Shale	3040	3195
Red Bed & Shale	30	640	Lime & Shale	3195	3360
Shale	640	860	Shale	3360	3560
Salt & Shale	860	1190	Sand	3560	3675
Anhydrite	1190	1400	Shale	3675	3815
Lime	1400	1705	Lime	3815	4210
Lime & Shale	1705	2290	Lime & Shale	4210	4390
Shale	2290	2410	Chert & Lime	4390	4645
Lime & Shale	2410	2645	Shale	4645	4775
Shale	2645	2690	Sand	4775	4818
Lime	2690	2765	Shale	4818	4859
Shale	2765	2820	TOTAL DEPTH	4859	
Lime	2820	3040			

RESULTS of INITIAL PRODUCTION TEST: Plugged and Abandoned 6/17/68.

15-077-20062-00-00

DRILLER'S LOG

COMPANY	Anadarko Production Company
CONTRACTOR	LEBEN DRILLING, INC.
FARM	Parsons F-1
LOCATION	C NW SE Section 23-31s-7w Harper County, Kansas
COMMENCED	6-3-68
COPLETED	6-17-68

0	30'	Sand
30	640	Red Bed
640	1190	Shale
1190	1225	Anhydrate
1225	1460	Shale, Lime
1460	1700	Lime, Shale
1700	1880	Lime
1880	2065	Lime, Shale
2065	2860	Shale, Lime
2860	3080	Lime, Shale
3080	3464	Shale, Lime
3464	3900	Lime, Shale
3900	4778	Lime
4778	4859	Sand
	<u>4859</u>	<u>RTD - D &amp; A</u>

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 20 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
06-20-1968

8 5/8" New 24# Surface casing set @ 637' with 350 sx 50-50  
Posmix HA-5 plus 100 sx common - 3% HA-5

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Parsons F-1 well, located C NW SE of Section 23, Township 31 South, Range 8 West, Harper County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite  
Leslie Kite

STATE OF KANSAS  
COUNTY OF BARTON SS

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 19, day of June, 1968.

Ulanda Nichols  
Ulanda Nichols

My Commission Expires  
April 1, 1968 7'