

15-077-20786-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Harper SEC. 22 TWP. 31S RGE. 7W E/W
Location as in quarters or footage from lines:

SW SW SE

		22	
		+	

Locate Well
correctly on above
Section Platt.

Lease Owner Kinetic Oil & Gas Exploration, Inc.
Lease Name Joslin Well No. 1
Office Address 2822 S. Uinta, Denver, Colorado 80231
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed March 12, 1982
Application for plugging filed 3/18/82
Plugging commenced 3/12/82
Plugging completed 3/12/82
Reason for abandonment of well or producing formation

Dry Hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice V. Leslie

Producing formation Depth to top bottom T.D. 4804'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		0'	266'	8-5/8"	259'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from feet
to feet for each plug set.

Plugged with 60 sacks cement at 1100';
40 sacks cement at 250'; solid bridge plug
and 10 sacks cement at 40'.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

John D. Knightley Agent (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
221 S. Broadway, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of March, 1982

[Signature]
Stella J. Lipps, Notary Public.

My Commission expires: March 12, 1983

RECEIVED
STATE CORPORATION COMMISSION
04-07-1982
APR - 7 1982
CONSERVATION DIVISION
Wichita, Kansas

15-077-20786-00-00

Kinetic Oil & Gas Exploration, Inc.
2822 S. Uinta
Denver, Colorado 80231

- Joslin #1
SW SW SE Sec. 22-11S-7W
Harper County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
221 S. Broadway, Suite 400
Wichita, Kansas 67202

Commenced: March 2, 1982
Completed: March 12, 1982

Drillers Log

Hard Red Bed	105
Red Bed	269
Red Bed & Shale	875
Shale	1202
Anhydrite	1230
Shale	1655
Shale & Shells	3500
Lime & Shale	3920
Lime	4057
Chert & Lime	4099
Lime	4747
Lime & Shale	4786
Shale & Sand	4800
Lime	4804 RTD

RECEIVED
STATE CORPORATION COMMISSION

APR - 7 1982

CONSERVATION DIVISION
Wichita, Kansas

04-07-1982