

15-077-30011-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Harper County, Sec. 19 Twp. 31 Rge. 7 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines C SE NW
Lease Owner Mack Oil Company
Lease Name Yoder Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 3-3-66 _____ 19____
Plugging completed 3-8-66 _____ 19____
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4412 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	265'	None
				4-1/2"	4412'	3608'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, sanded hole to 3975' and dumped 3 sacks of cement @ 3975' with dump bailer. Pulled 4 1/2" casing, mudded hole to 260', set rock bridge to 250' and dumped 25 sacks of cement @ 250'. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement from 30' to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

03-17-1966
MAR 17 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of March, 19 66

Milton J. Volin

Notary Public.

My commission expires May 20, 1968

15-077-30011-00-00

MACK OIL COMPANY
Duncan, Oklahoma

DRILLERS WELL LOG

#1 Yoder

Commenced R. D.: 6-12-65
Completed R. D.: 7-9-65
Total Depth: 4785'

C SE NW Section 19-31S-7W
Harper County, Kansas
Elevation: 1552' Kelly Bushing
Initial Production:
Contractor: Mack Oil Company

<u>STRATA</u>	<u>DEPTH</u>
Top Soil & Clay	0 - 10'
Sand	10 - 100
Shale	100 - 265
Red Bed & Shale	265 - 495
Shale	495 - 1270
Shale & Lime	1270 - 1421
Lime	1421 - 2000
Shale & Lime	2000 - 2160
Lime & Shale	2160 - 2370
Shale & Lime	2370 - 2650
Lime & Shale	2650 - 2980
Shale with Lime Streaks	2980 - 3245
Lime	3245 - 3418
Lime Streaks with Shale	3418 - 3640
Douglas Sand	3640 - 3700
Lime & Shale	3700 - 3854
Lime	3854 - 4380
Miss. Lime	4380 - 4390
Cherty Lime	4390 - 4593
Lime	4593 - 4602
Lime & Shale	4602 - 4698
Lime	4698 - 4758
Sand	4758 - 4785'

RECEIVED
STATE CORPORATION COMMISSION
MAR 17 1966
CONSERVATION DIVISION
Wichita, Kansas
03-17-1966

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

MACK OIL COMPANY

By Jack Maronde
Jack Maronde

Signed and sworn to in my presence this 15th day of July, 1965, by Jack Maronde, representative of Mack Oil Company.

Elizabeth F. Nice
Elizabeth F. Nice, Notary Public

My commission expires September 21, 1968