

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-077-10002-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Harper County. Sec. 19 Twp. 31S Rge. 7 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW NE SE

Lease Owner Continental Oil Company

Lease Name B. Stevens Well No. One

Office Address Box 161, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 5-4 1960

Application for plugging filed 5-4 1960

Application for plugging approved 5-4 1960

Plugging commenced 5-4 1960

Plugging completed 5-5 1960

Reason for abandonment of well or producing formation No commercial shows of oil or gas encountered.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Fred Hample

Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 4830 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	FUT IN	PULLED OUT
				8 5/8"	251'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/mud to 240 feet. Dumped in 1/4 sack of hulls and set plug at 240 feet. Spotted 15 sacks of cement thru drill pipe on top of plug. Filled hole w/mud to 35 feet. Dumped 1/4 sack of hulls and set plug at 35 feet. Filled hole to surface w/10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 9 1960

CONSERVATION DIVISION
Wichita, Kansas

05-09-1960

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Peel Brothers, Inc.

Address Hoisington, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Mr. O. F. Weber (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) O. F. Weber

Box 161, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of May, 1960

Jack D. Munn
Notary Public.

My commission expires August 1, 1960

15-077-10002-00-00 19-31-4W

MILLERS' LOG

Well Owner: Continental Oil Company
 Well Name: Stevens Well No. 1
 Commenced: 4/17/60
 Completed: 5/3/60
 Total Depth: 4830'
 Casing: 8 5/8" @ 248' con.

2130' F/EL 990' F/EL
 Sec. 19, Twp. 31N, Rge. 7W
 County, Harper,
 Kansas
 Elevation: GL-1565, RB-1574

Contractor: Peal Brothers, Inc. Production: Dry

Figures below indicate bottoms of formations:

Sand	0-	70
Red bed and shale		680
Shale and shells		1405
Line and shale		1640
Line		2125
Line and shale		2910
Line		2985
Line and shale		3885
Line		3980
Line and chert		4000
Line		4080
Line and shale		4195
Line		4250
Shale and line		4285
Line		4625
Line and shale		4796
Shale		4788
Simpson Sand		4830
T.D.		4830

RECEIVED
STATE CORPORATION COMMISSION

OCT 8 1962

CONSERVATION DIVISION
Wichita, Kansas

10-08-1962

This is to certify that the above information is to the best of our knowledge, true and correct.

PEAL BROTHERS, INC.

Handwritten signature

WITNESSED AND SWORN to before me this 6 day of May, 1960.

My commission expires: April 27, 1964

Handwritten signature
Notary Public

15-077-10002-00-00
 WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


COPY

Company. CONTINENTAL OIL COMPANY
 Farm. Stevens No. 1

SEC. 19 T. 31 R. 7
 NW NE SE

Total Depth. 4830'
 Comm. 4/17/60 Comp. 5/5/60
 Shot or Treated.
 Contractor. Peel Brothers, Inc.
 Issued. 6/25/60

County Harper
 KANSAS



CASING:
 8 5/8" 248' cem.

Elevation. 1574 BB

Production. Dry

Figures Indicate Bottom of Formations.

sand	70
red bed & shale	680
shale & shells	1405
lime & shale	1640
lime	2125
lime & shale	2910
lime	2985
lime & shale	3885
lime	3980
lime & chert	4000
lime	4080
lime & shale	4135
lime	4250
shale & lime	4285
lime	4625
lime & shale	4756
shale	4768
Simpson sand	4830
Total Depth	

*This well washed
 down by J.E. Newman
 in 1960*

TO.S: SCOUT	
Heebner	3340
Douglas	3436
Kansas City	3887
Base Kansas City	4129
Mississippi	4405
Kinderhook	4661
Simpson Dolomite	4769
Simpson Sand	4791

RECEIVED
 STATE CORPORATION COMMISSION

MAY 3 - 1966

CONSERVATION DIVISION
 Wichita, Kansas

05-03-1964