


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

15-077-20218-10-00
Form CP-4
WELL PLUGGING RECORD

Harper County. Sec. 19 Twp. 31S Rge. 7W (E) (W)X

Location as "NE/CNW/SW" or footage from lines SE NE NE
Lease Owner Mr. John E. Loughran Oil Exploration
Lease Name Smith Well No. No. 3
Office Address 4904 Sunset Drive, Ralston, Nebraska 68127
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed October 17 19 73
Application for plugging filed October 17 19 73
Application for plugging approved October 17 19 73
Plugging commenced October 17 19 73
Plugging completed October 17 19 73
Reason for abandonment of well or producing formation D & A



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G.R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4780 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	270'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole w/heavy mud to 270' & Set plug w/25 sx cmt. Filled hole w/heavy mud to 40' & Plug w/1/2 sk. hulls & 10 sx. cement to bottom of cellar. 2 sx cmt. in rathole.

RECEIVED
STATE CORPORATION COMMISSION

NOV 1 1973

CONSERVATION DIVISION
Wichita, Kansas

11-01-1973

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Company
Address 1720 Wichita Plaza, Wichita, Kansas 67202


STATE OF Kansas, COUNTY OF Sedgwick, ss.
Jim Farrice (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Farrice
1720 Wichita Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of October, 19 73

Linda N. Dickens
Notary Public.

March 8, 1977



15-077-20218-00-00

DRILLERS LOG

No. 3 Smith

CASING RECORD:

8-5/8" @ 270'
w/200 sx cement

TOTAL DEPTH: 4780'

COMPANY: Mr. John E. Loughran

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: October 2, 1973

COMPLETED: October 17, 1973

DESCRIPTION:

SE NE NE
19-31S-7W
Harper County,
Kansas

ELEVATION: 1558' Gr

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	50	
Rock & Shale	50	270	
Red Shale	270	300	
Shale	300	1025	
Shale & Shells	1025	1355	
Shale & Lime	1355	1890	
Shale	1890	1955	
Shale & Lime	1955	3310	
Lime	3310	4383	
Shale & Chert	4383	4387	
Lime & Chert	4387	4565	
Cherty Lime	4565	4640	
Lime & Chert	4640	4740	
Lime & Shale	4740	4765	
Lime	4765	4780	

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1973
CONSERVATION DIVISION
Wichita, Kansas
11-01-1973

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jim Farrice
Jim Farrice

Subscribed and sworn to before me this 19th day of October, 1973.

Linda N. Dickens
Notary Public

My Commission Expires:

March 8, 1977

