


15-077-20260-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

Harper County. Sec. 19 Twp. 31S Rge. 7 (E) 7 (W)  
Location as "NE/CNW&SW" or footage from lines C NW NE  
Lease Owner Zetco Petroleum Co., Inc.  
Lease Name Smith Well No. 1  
Office Address 357 Lulu - Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 20, 1974  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced May 19, 1974  
Plugging completed May 19, 1974  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein of Attica  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4800 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface					
	Casing	0	247'	8 5/8"	247'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud from total depth to 2230'  
a plug, 35 sacks cement, mud to 40'  
a plug, bridged and 10 sacks cement  
to base of cellar - 2 sacks in rat  
hole. Job completed at 2:00 P.M.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 29 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
05-29-1974


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Allied Cementing Company, Inc.  
Address P. O. Box 31, Russell, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
William J. Froelich, Jr. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Search Drilling Company

(Signature) William J. Froelich, Jr.  
William J. Froelich, Jr.  
P. O. Box 18148 / Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 21st. day of May, 1974



Maxine Dressen  
Notary Public.

15-077-20260-00-00

DRILLERS LOG

SMITH NO. 1

<u>CASING RECORD:</u> 8 5/8" set at 247' w/225 sax cement	<u>OPERATOR:</u> ZETCO PETROLEUM CO., INC.	<u>DESCRIPTION:</u> C NW NE Sec.19-31S-7W Harper County, Kansas
<u>TOTAL DEPTH:</u> 4800'	<u>CONTRACTOR:</u> SEARCH DRILLING COMPANY	
	<u>COMMENCED:</u> May 11, 1974	
	<u>COMPLETED:</u> May 20, 1974	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	70	
Red Bed Shale	70	247	
Shale, Shells and Sand	247	928	
Shale	928	1303	
Lime	1303	1550	
Lime	1550	1850	
Lime and Shale	1850	2105	
Shale and Lime	2105	2365	
Shale and Lime	2365	2660	
Lime and Shale	2660	2915	
Broken Lime and Shale	2915	3180	
Lime and Shale	3180	3370	
Lime and Buttons	3370	3799	
Lime	3799	4101	
Lime	4104	4204	
Lime and Shale	4204	4298	
Lime	4298	4383	
Lime	4383	4400	
Chert	4400	4605	
Chert and Lime	4605	4678	
Lime	4678	4731	
Lime with Chert	4731	4775	
Shale and Lime and Sand	4775	4800	

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 29 1974  
CONSERVATION DIVISION  
Wichita, Kansas

05-29-1974

D & A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SEARCH DRILLING COMPANY

William J. Froelich Jr.  
William J. Froelich Jr.

Subscribed and sworn to before me this 21st day of May, 1974

Maxine Dressen  
Maxine Dressen Notary Public

