


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-077-00204-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Harper County, Sec. 8 Twp. 31 Rge. (E) 7 (W)

Location as "NE/CNW/SW" or footage from lines C SE NW NW  
Lease Owner Cooperative Refinery Association  
Lease Name Rutledge "A" Well No. 1  
Office Address Box 765 Gt. Bend, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed 9-29 1958  
Application for plugging filed 9-30-58 1958  
Application for plugging approved 10-1 1958  
Plugging commenced 9-29 1958  
Plugging completed 9-29 1958

Reason for abandonment of well or producing formation  
Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Verbal permission obtained.

Name of Conservation Agent who supervised plugging of this well Fred Hampel

Producing formation Depth to top Bottom Total Depth of Well 4833 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	288'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 240', spotted 20 sc. cement thru drill pipe at 240', pulled drill pipe up to 40', spotted 10 sx. at 40', laid down drill pipe, used 5 sx. cement in fill hole.

Name of Plugging Contractor Shields Drlg. Company  
Address Russell, Ks.

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Marvin D. Sullivan (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Marvin D. Sullivan  
Box 765 Gt. Bend, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 14 day of November, 1958

My commission expires Sept. 24. 1960

Yvonne Adams Notary Public.

PLUGGING  
FILE SEC. 8 T. 31 R. 7W  
BOOK PAGE 133 LINE 22

RECEIVED  
STATE CORPORATION COMMISSION  
11-15-1958  
NOV 15 1958  
CONSERVATION DIVISION  
Kansas

15-077-00204-00-00

DRILLERS LOG

RUTLEDGE "A" #1

Loc: C SE NW NW  
Sec: 8-31S 7W  
Harper County, Kansas  
Operator: Cooperative Refinery Ass'n.  
Contractor: Shields Drilling Company

Elevation: 1636 KB  
Casing: 8-5/8" @288' w/225 sx.

5 1/2" @(Diden't set)

Comm: 9-9-58 Comp: 9-30-58  
Total Depth: 4833'

<u>From</u>	<u>To</u>	<u>Formation</u>
0	117	Sand
117	283	Sand Streaks, redbed & shale
283	840	Shale with sand streaks
840	1290	Shale
1290	1455	Shale with lime streaks
1455	1625	Lime & Shale
1625	1770	Lime w/shale streaks
1770	1882	Lime w/shale streaks
1882	2020	Lime w/shale streaks
2020	3200	Shale w/lime
3200	3343	Lime
3343	3740	Shale
3740	3885	Shale w/lime
3885	3980	Lime w/shale
3980	4428	Lime
4428	4622	Lime w/chert
4622	4822	Lime
4822	4833	Simpson Sand
4833		T.D.

(STATE OF KANSAS )

(COUNTY OF BARTON )

RECORDED  
10-01-1958  
OCT 1 1958

I hereby certify that the above is a true and correct copy of the log on the Rutledge "A" #1 well, located C SE NW NW of Section 8-31S 7W, Harper County, Kansas.

Morris D. Sullivan

Subscribed and sworn to before me this day of September 30, 1958

Yvonne Adams

My commission expires: Sept. 24, 1960

PLUGGING  
FILE SEC 8 T 31 R 7W  
BOOK PAGE 133 LINE 22