


15 077-00236-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Harper County. Sec. 9 Twp. 31S Rge. 7 (XX) (W)

Location as "NE/CNW/SW" or footage from lines NE NE NW  
Lease Owner L. C. Smitherman Oil Producer  
Lease Name Meyer Well No. 1  
Office Address Box 627 - Augusta, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-18 19 56  
Application for plugging filed 5-18 19 56  
Application for plugging approved 5-18 19 56  
Plugging commenced 5-18 19 56  
Plugging completed 5-18 19 56  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4965 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Hubner	Water	3320	174			
Kansas City	"	3843	2274			
Base Kansas City	"	4070	2474			
Mississippi	"	4381	2785			
Kinderhook	"	4661	3065			
Dolomite	"	4786	3190			
Simpson	"	4796	3200			
Arbuckle	"	4939	3343			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled with mud to 200'. Halliburton plug set and cemented with 20 sacks. Mud to 35'. Halliburton plug set with 10 sacks cement. Hole filled with mud.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor L. C. Smitherman Drilling Company  
Address Box 627 - Augusta, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.  
Joe W. Cain (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe W. Cain  
Box 627 - Augusta, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of May, 19 56

Ruth H. Carter  
Notary Public.

My commission expires October 23, 1958.

PLUGGING  
FILE SEC. 9 T 31 R 7 W  
BOOK PAGE 62 LINE 43

Company - L. C. Smitherman Oil Producer Location: NE NE NW, Sec. 9-31S-7W, Harper  
 Contractor - L. C. Smitherman Drlg. Co. County, Kansas  
 Elevation: 1596 KB  
 Commenced - 4-26-56 Casing: 8 5/8" - 200' cemented W/265 Sks.  
 Completed - 5-18-56  
 Total Depth - 4965'  
 Initial Prod. - D & A

Figures Indicate Bottoms of Formations:

Depth	Formation	Depth	Formation
0 - 50	Sand	4460-4634	Lime & Chert
50 - 95	Red Rock & Shale	4634-4660	Lime & Shale
95 - 140	Shale & Shells	4660-4712	Lime & Sand W/Shale Strk.
140 - 200	Lime & Shale	4712-4743	Shale & Lime
200 - 270	Shale & Shells	4743-4773	Sandy Shale & Lime
270 - 542	Red Rock	4773-4807	Lime & Shale, Simpson
542 - 1200	Shale & Shells - Red Rock		Sand @ 4786'
1200 - 1250	Shale & Shells	4807-4814	Sand
1250 - 1443	Sand & Sandy Lime	4814-4833	Sand & Lime-Simpson
1443 - 1592	Shale & Anhydrite	4833-4853	Sand & Lime
1592 - 1835	Lime Ft. Riley	4853-4965	Lime & Sand
1835 - 2000	Lime & Shale	4965-R.T.D.	
2000 - 2115	Shale & Lime		
2115 - 2230	Sandy Shale		
2230 - 2380	Shale & Lime		
2380 - 2448	Lime & Shale		
2448 - 2565	Sand & Shale		
2565 - 2936	Shale & Lime		
2936 - 2965	Lime & Shale		
2965 - 2995	Lime		
2995 - 3080	Sandy Shale		
3080 - 3180	Sand		
3180 - 3254	Sand & Lime		
3254 - 3275	Shale & Sand		
3275 - 3344	Hebner Shale & Sand		
3344 - 3434	Lime & Shale		
3434 - 3544	Shale & Lime		
3544 - 3581	Shale		
3581 - 3589	Sand & Shale		
3589 - 3653	Shale & Lime - Sandy		
3653 - 3722	Sandy Shale		
3722 - 3825	Lime & Shale		
3825 - 3862	Shale & Lime		
3862 - 3942	Lime & Shale		
3942 - 3962	Lime		
3962 - 3992	Lime & Chert - Shale		
3992 - 4022	Lime & Shale		
4022 - 4079	Lime		
4079 - 4100	Lime & Shale		
4100 - 4128	Lime		
4128 - 4381	Lime & Shale		
4381 - 4395	Chat		
4395 - 4410	Chat & Chert		
4410 - 4460	Lime (Miss.)		

We hereby certify the above and foregoing to be a true and correct copy of the Log on the Meyer #1, located in the NE NE NW, Section 9-31S-7W, Harper County, Kansas.

L. C. SMITHERMAN DRILLING COMPANY

*Jac. W. Carr*

Subscribed and sworn to before me this 25th day of May, 1956.

*Ruth H. Carter*  
 Notary Public

My commission expires October 23, 1958.

