

1 050883

86

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,098-0000

SW SE NE, SEC. 8, T 16 S, R 26 (W)
2970 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5190

Lease Name Nuttle Well # 1

Operator: Sabre Exploration, Inc.
Name & Address 127 East Second
Wichita, KS 67202

County Ness 145.44
Well Total Depth 4475 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 240

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Republic Drilling, Inc. License Number 9943

Address 310 W. Central, #214, Wichita, KS 67202

Company to plug at: Hour: 3:30 p.m. Day: 16 Month: 2 Year: 19 87

Plugging proposal received from Steve Low

(company name) Republic Drilling, Inc. (phone) 316-264-0079

Elevation 2644'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2060-2102'

1st plug at 2070' with 50 sx cement, 2nd plug at 1290' with 80 sx cement,

3rd plug at 270' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 6 p.m. Day: 16 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2070' with 50 sx cement,

2nd plug at 1290' with 80 sx cement,

3rd plug at 270' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

STATE CORPORATION COMMISSION

2-19-87
FEB 19 1987

CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lacy
(TECHNICIAN)

INVOICED

DATE 2-20-87

INV. NO. 16188 MAR 27 1987

2-16

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 2 9 87 month day year 400

API Number 15-135-23,098-0000

OPERATOR: License # 5190 Name Sabre Exploration, Inc. Address 127 East Second City/State/Zip Wichita, Kansas 67202 Contact Person Matthew W. Totten Phone (316) 264-2635

SW SE NE... Sec. 8... Twp. 16.. S, Rg. 26... East West 2970 Ft. from South Line of Section 990 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet County Ness

CONTRACTOR: License # 9943 Name Republic Drilling, Inc. City/State Wichita, Kansas

Lease Name Nuttle Well # 1 Ground surface elevation 2644 feet MSL

Well Drilled For: X Oil SWD Infield Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

Depth to bottom of fresh water 150 Depth to bottom of usable water 1050 126.5

Surface pipe by Alternate: 1 2 X Surface pipe planned to be set 240

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Conductor pipe required Projected Total Depth 4600 feet

Formation Mississippian

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date Signature of Operator or Agent Matthew W. Totten Title President

For KCC Use: Conductor Pipe Required 200 feet; Minimum Surface Pipe Required 200 feet per Alt. This Authorization Expires 8-6-87 Approved By 2-6-87

SPAD 2-9-87 Don Abel 280+

SW SE NE... Sec. 8... Twp. 16.. S, Rg. 26... East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 2050 feet depth with 50 sxs of 60/40 pozmix (6% gel)
2nd plug @ 1300 feet depth with 50 sxs of 60/40 pozmix (6% gel)
3rd plug @ 270 feet depth with 50 sxs of 60/40 pozmix (6% gel)
4th plug @ 40 feet depth with 10 sxs of 60/40 pozmix (6% gel)
5th plug @ feet depth with sxs of
(2) Rathole with 15 sxs (b) Mousehole with sxs

PUSHER Steve Low v Republic
TD #475 FORMATION MISS
SURFACE PIPE 8 5/8" @ 240
ANHYDRITE 2060-2102 ELEVATION 2644
STARTING TIME & DATE 3:30 pm 2/16/87
COMPLETION TIME & DATE 6:00 pm 2/16/87
1st PLUG @ 2070 FT. W/ 50 SX
2nd PLUG @ 1290 FT. W/ 80 SX
3rd PLUG @ 270 FT. W/ 40 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY Halliburton
TECHNICIAN Lacey Sawpart
Orders by Dan Goodrow

STATE CORPORATION COMMISSION
FEB 19 1987
CONSERVATION DIVISION
Wichita, Kansas