

To: 1 070710
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-8

API NUMBER 15-135-22,759-000
SW NE SE, SEC. 8, T 16 S, R 26 W/E
1650 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Operator: Texas Energies, Inc.

Name & Address P.O. Box 947

Pratt, KS 67124

Lease Name Deighton Well # 1-8

County Ness 149.50

Well Total Depth 4600 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 346

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Texas Energies, Inc. License Number 5087

Address P.O. Box 947, Pratt, KS 67124

Company to plug at: Hour: 10:30 a.m. Day: 8 Month: 8 Year: 19 89

Plugging proposal received from Mark Stevenson

(company name) Texas Energies, Inc. (phone) 316-672-7514

were: 4 1/2" at 4596' PBTD 4597' Perfs at 4164-69, 4440-43'

1st plug pressure test 4 1/2" X 8 5/8" annulus to 500 psi. If pressure will not hole, pump 40 sx econolite down annulus.

2nd plug tie on to 4 1/2". Pump 400 lbs. hulls followed by 110 sx econolite to fill production casing from perforations to surface.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:15 a.m. Day: 8 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT Perforated at 1212', cemented to 0' w/300 sx cement.

Pressured annulus to 1500 lbs., would not take.

1st plug pumped 400 lbs. hulls and 150 sx Thriftymix down 4 1/2" casing.

Maximum pressure 500 psi and shut in 0 psi.

RECEIVED
STATE CORPORATION COMMISSION
8-11-89
AUG 11 1989

Remarks: Used Thriftymix by B.J. Titan. No casing recovery.

(If additional description is necessary, use BACK of this form.)

(did / did not) observe this plugging.

INVOICED

DATE 8-17-89

INV. NO. 25638

8-8

Signed Dan Goodrow
(TECHNICIAN)