

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-01002-00-01
Spot: NENWNW Sec/Twnshp/Rge: 31-19S-19W
330 feet from N Section Line, 990 feet from W Section Line
Lease/Unit Name: MARESCH Well Number: 1
County: RUSH Total Vertical Depth: 4370 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH STREET
NEWTON, KS 67114

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 355
Production: Size 5.5 feet: 4369
Liner: Size _____ feet:

\$142.03

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/29/2001 1:50 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: CLAY WATCHOUS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 799-1000

Proposed Plugging Method: SQUEEZED FROM 800' TO SURFACE WITH 300 SX CMT. CMT FELL BACK AND REFILLED WITH 35 SX CMT.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 06/29/2001 2:30 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PERFS AT 4190-4200' & 4205-4211'. 8 5/8" ANNULUS CEMENTED FROM 800' TO SURFACE WITH 335 SX CMT. SANDED PERFS TO 3980' & 4 SX CMT WITH BAILER. SHOT CASING AT 1995' (PRESSURE RELIEF HOLES) AND PUMPED CASING FULL WITH 135 SX CMT. SHUT IN WITH 400#. CHECKED ANNULUS. CASING FULL OF CMT.

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 6 2001

7-6-01
CONSERVATION DIVISION

INVOICE

DATE 7-6-01

INV. NO. 2002060022

Remarks: USED 60/40 POZMIX 6% GLE BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Steve Hurst
(TECHNICIAN)

JUL 05 2001

Form CP-2/3

MP