

1 050725

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,339 - 0000

SW NE SE, SEC. 17, T 19 S, R 20 (W)  
1650 feet from (S) section line  
990 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5430

Lease Name R. L. Young Well # 3

Operator: Energy Three, Inc.

County Rush

Name & Address P. O. Box 1505

Well Total Depth 4489 Mississippi 145.89 feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 631

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Big Three Drilling, Inc. License Number 5836

Address P. O. Box 52, Gorham, KS 67640

Company to plug at: Hour: 7:00 pm Day: 13 Month: December Year: 19 85

Plugging proposal received from Stan Lovelady

(company name) Big Three (phone) 913-637-5487

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1530-59' Elevation N/A

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 30' below the base of the surface pipe with 50 sx cement  
solid bridge -

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9:15 pm Day: 13 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1557' with 50 sx cement, 2nd plug at 660' with 50 sx  
cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with  
10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 7th plug to circulate  
mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

STATE CORPORATION COMMISSION

Signed Richard W. Lacey  
(TECHNICIAN)

DATE DEC 27 1985

DEC 27 1985

INV. NO. 11734

12-27-85  
CONSERVATION DIVISION  
Wichita, Kansas

CARD MUST BE TYPED

State of Kansas

NOTICE OF INTENTION TO DRILL

CARD MUST BE SIGNED

(see rules on reverse side)

Starting Date NOVEMBER 29 1985 month day year

API Number 15-165-21,339-0000

OPERATOR: License # 5430 Name ENERGY THREE, INC. Address P.O. Box 1505 City/State/Zip GREAT BEND, KANSAS 67530 Contact Person CHARLES DIXON Phone AC316-792-5968

SW NE SE 17 Sec. 19 S, Rg. 20 East X West 1650 Ft. from South Line of Section 990 Ft. from East Line of Section (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5836 Name B.I.G. THREE DRILLING, INC. City/State GORHAM, KANSAS 67640

Nearest lease or unit boundary line 990 feet County RUSH Lease Name R.L. YOUNG Well # 3 Ground surface elevation feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Surface pipe by Alternate: 1 X 2 Depth to bottom of fresh water 260-360 Depth to bottom of usable water 590 Surface pipe planned to be set 590 (8 5/8") Projected Total Depth 4500 feet Formation M.I.S.S.I.S.S.I.P.P.I

Well Drilled For: X Oil SWD X Infield Type Equipment: X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. cementing will be done immediately upon setting production casing. Date 11-18-85 Signature of Operator or Agent Title EXEC. VICE-PRES.

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required feet per 1 2 This Authorization Expires 5-19-86 Approved By

590' of 58 9/8 on 12/4/85

PUSHER Stan Kovelady TD 4489 FORMATION MISS. SURFACE PIPE 8 7/8 @ 631 ANHYDRITE 1530 ELEVATION NA STARTING TIME & DATE 12-13-85 9:15 COMPLETION TIME & DATE 1st PLUG @ Anhydrite FT. W/ 50 SX 2nd PLUG @ Surface FT. W/ 50 SX 3rd PLUG @ 40 FT. W/ 50 SX + 10 SX 4th PLUG @ 1 FT. W/ SX RAT HOLE CIRCULATED W/ 10 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ CEMENT COMPANY ALLIED TECHNICIAN LACOX 1st 1557' w/ 50sx - 2nd 660 w/ 50sx - 3rd 40' - 10sx - 6th 10m-10R 6/4 6% -

DEC 27 1985 12-27-85 CONSERVATION DIVISION