

1 030522

API NUMBER 15- 165-21,316 -0000 *R*

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C S/2 SW NE, SEC. 17, T 19 S, R 20 W/X
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2970 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5430

Lease Name R. L. Young Well # 2

Operator: Energy Three, Inc.

County Rush 147.23

Name & Address

P. O. Box 1505

Well Total Depth 4530 Mississippi feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 637

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Big Three Drilling Co., Inc. License Number 5836

Address P. O. Box 52, Gorham, KS 67640

Company to plug at: Hour: 11:45 am Day: 14 Month: September Year: 19 85

Plugging proposal received from Stan Lovelady

(company name) Big Three (phone) 913-628-8649

to fill hole with heavy mud and spot cement through drill pipe Elevation 2292'

Anhydrite 1537-1565

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 30' out of the base of the surface pipe with 40 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:45 pm Day: 14 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1555' with 50 sx cement, 2nd plug at 655' with 40 sx

cement, 3rd & 4th plugs - solid bridge- hulls - plug at 40' -- cement to surface with 10

sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse

hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1985
9-23-85

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (copy) did not observe this plugging.

Signed *Steve Durrant*
(TECHNICIAN)

DATE SEP 24 1985

INV. NO. 10228