

2040200

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-077-20933-00-00
C-NE-S6 SEC. 6, T. 31 S., R. 7 W/6

1980 feet from N/S section line
660 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Hunter Well # F-1

Operator: TXO Prod. Corp

County Harper 156.00

Name & Address 200 W. Douglas.

Well Total Depth 4800 feet

Sut 300

Conductor Pipe: Size _____ feet

Wichita Ks. 67202

Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clark Corp. License Number _____

Address Medicine Lodge

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Elmo Morganstein

(company name) Clark Corp. (phone) _____

were: _____

PBTD 4547 Sand to 4342 & 4 SKS.

4 1/2 4542 2 Hull 12 gel 125 SX ⁶⁰/₄₀

Perf 4382-92 Rec 3750

300 150

Plugging Proposal Received by W. Kirkpatrick
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 1310 Day: 5 Month: 7 Year: 19 85

ACTUAL PLUGGING REPORT Sand was dumped inside the 4 1/2 casing

to plug off the perforations. The top of the sand is 4342'

with a 5 sack cap of cement on top of the sand. The

4 1/2 was shot off at 3750 and recovered. The top

was squeezed thru the 8 5/8 surface pipe by pumping

2 sacks of hulls 2 sacks of gel & 125 sacks of 60/40 Poz-mix

Remarks: Cement Sun Cementing #283539 MX300 SF 50

(If additional description is necessary, use BACK of this form.)

INVOICED

(did, did not) observe this plugging.

DATE 7-19-85

INV. NO. 9031

W. Kirkpatrick (TECHNICIAN) Signature

JUL 16 1985
07-16-1985
CONSERVATION DIVISION
Wichita, Kansas

RO