

1060178

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,511-0000

NE NW SW, SEC. 5, T 16 S, R 26 W/E

2310 feet from ~~N~~/S section line

990 feet from ~~W~~/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5190

Lease Name Basinger Well # 1

Operator: Sabre Exploration, Inc.

County Ness

Name & Address 730 Broadway Plaza

Well Total Depth 4542 147.61 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Wheat State Oilfield Service License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 11:00 pm Day: 19 Month: February Year: 19 84

Plugging proposal received from Greg Bailey

(company name) Wheatstate (phone) 316-672-7514

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 2050' with 50 sx cement

2nd plug at 1020 with 50 sx cement

3rd plug at 380' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:15 am Day: 20 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2050' with 50 sx cement, 2nd plug at 1020' with 50

sx cement, 3rd plug at 380' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with'

15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 29 1984

2-29-84

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Buie

(If additional description is necessary, use BACK of this form.)

I (the operator) observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

INVOICED

DATE 3-8-84
INV. NO. 0617

3-20