

1 060538

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-21,235-0000

TECHNICIAN'S PLUGGING REPORT

E/2 NW NW, SEC. 5, T 16 S, R 26 W/K

4290 feet from S section line

4290 feet from E section line

Operator License # 5886

Lease Name Basinger C Well # 1

Operator: Chief Drilling Co., Inc.

County Ness 143.91

Name & Address 905 Century Plaza Building

Well Total Depth 4428 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 277 ✓

T/A LIST

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 5:00 pm Day: 11 Month: April Year: 19 85

Plugging proposal received from Ronnie Hoover

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4417' Open Hole

1st plug sand back to 4370' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Robert B. Tarbutton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6:00 pm Day: 11 Month: April Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4370' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 150 sx cement.

RECEIVED STATE CORPORATION COMMISSION

APR 23 1985 4-23-85 CONSERVATION DIVISION Wichita, Kansas

Maximum pressure 500 psi and shut in 200 psi

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. Recovered 2335' 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

(If possible, observe this plugging.)

INVOICED

Signed Paul A. Luthie (TECHNICIAN)

DATE 5-2-85 INV. NO. 7912