

To: 1 070028
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,025 0000

NE NE SE, SEC. 15, T 16 S, R 26 W/E

2310 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8572

Lease Name Martin Well # 1

Operator: The Reach Group

County Ness 148.30

Name & Address 229 E. William, Suite 500

Well Total Depth 4563 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 329

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Midwest Casing Pulling Service License Number 6497

Address P. O. Box F, Sublette, KS 67877

Company to plug at: Hour: 3:30 pm Day: 2 Month: October Year: 19 85

Plugging proposal received from Ed Eves

(company name) Midwest (phone) 316-675-8349

were: 4 1/2" at 4560' Perfs at 4505-10

1st plug pump 2 sx hulls and 20 sx cement to bottom.

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 15 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 175 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 5:20 pm Day: 2 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement to 4230', 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 15 sx gel, 1 sack hulls, released 8 5/8" rubber wiper plug and pumped 175 sx cement.

Maximum pressure 1000 psi and shut in 400 psi

Remarks: Recovered 2600' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-15-85

STATE CORPORATION COMMISSION

Signed Dan Goodhue

(TECHNICIAN)

INV. NO. 10579

10-10-85
OCT 10 1985