

1060264

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,153-0000

NW NW NE, SEC. 12, T 16 S, R 26 (W 26)
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5023

Lease Name Herrman Well # 1

Operator: Kansas Petroleum, Inc.
Name & Address: 225 North Market, Suite 310
Wichita, KS 67202

County Ness

Well Total Depth 4490 145.93 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 315

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hembree Well Service License Number 6907

Address 302 East Sycamore, Ness City, KS 67560

Company to plug at: Hour: noon Day: 10 Month: July Year: 19 84

Plugging proposal received from Bill Luck

(company name) Hembree Well Service (phone) 913-798-3408

were: 4 1/2 set at 4485' Perfs 4077-81' DV at 1800'

1st plug pumped 10 sx cement to bottom 2nd plug at 4000' with 10 sx cement

Pumped 10 sx gel filling hole with heavy mud

3rd plug at 1800' with 25 sx cement 4th plug at 1200' with 25 sx cement
solid bridge

5th plug at 600' with 25 sx cement 6th plug hulls - plug at 40' -- cement to surface
with 10 sx cement

Plugging Proposal Received by Paul A. Luthie (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:00 pm Day: 10 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4485' Perfs at 4077' - 81' DV at 1800'

1st plug pumped 10 sx cement to bottom, 2nd plug at 4000' with 10 sx cement, pumped 10
sx gel filling hole with heavy mud, 3rd plug at 1800' with 25 sx cement, 4th plug at

1200' with 25 sx cement, 5th plug at 600' with 25 sx cement, 6th & 7th plugs - solid
bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

Remarks: Used 50/50 Pozmix 2% gel by Allied.

(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

7-12-84
JUL 12 1984

CONSERVATION DIVISION
Wichita, Kansas

Signed Paul A. Luthie (TECHNICIAN)

INVOICED

DATE 7-18-84

INV. NO. 2554