

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-21840-00-00
Spot: CE2NWNE Sec/Twnshp/Rge: 10-16S-26W
4620 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: LEVI Well Number: 4
County: NESS Total Vertical Depth: 4560 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Conductor Pipe: Size feet: \$148.20
Surface Casing: Size 8.625 feet: 319 WITH 200 SX CMT
Production: Size 5.5 feet: 4547 WITH 200 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/12/2002 9:40 AM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: RUN TUBING TO 4028' & PUMP 40 SX CMT WITH 200# HULLS. PULL TUBING TO 1690' & PUMP 40 SX CMT. PLUG AT 1200' WITH 120 SX CMT. CIRCULATE CMT TO SURFACE. PUMP 10 SX CMT TO TOPP OFF. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/12/2002 3:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:


OPEN HOLE. DV TOOL @ 2047' WITH 400 SX CMT. RAN TUBING TO 4028' & PUMPED 40 SX CMT WITH 200# HULLS. BOTTOM WAS SANDED IN AND COULDN'T GET TUBING DOWN HOLE ANY FURTHER. PULLED TUBING TO 1609' & PUMPED 40 SX COMMON CMT WITH 3% CC. WAITED 3 HOURS. LOGGED HOLE. FOUND 40 SX PLUG AT 1416'. LOGGED FROM THERE UP. CMT WAS BEHIND PIPE TO SURFACE. RAN TUBING TO 1200' & PUMPED 120 SX CMT. CIRCULATED TO SURFACE. PULLED TUBING AND PUMPED 10 SX CMT. TOPPED OFF. TIED ONTO BACKSIDE AND PUMPED 150 SX CMT. PRESSURED TO 500#. SHUT IN WITH 500#.

11-18-02
NOV 18 2002
KCC WICHITA

Remarks: USED COMMON & 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Michael Maier
(TECHNICIAN)

INVOICED
DATE 11-19-02
WV. NO. 2003060833