

To: 1 030706
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,906 GCGD

NE NW NW, SEC. 18, T 16 S, R 26 W
4950 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6827

Lease Name Norton Well # 1A

Operator: Robert L. Shaw
Name & Address 2770 Bermuda Circle
Colorado Springs, CO 80917

County Ness 149.50

Well Total Depth 4600 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 159

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pulling License Number 4635

Address P. O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10:00 am Day: 1 Month: May Year: 19 86

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pulling (phone) 316-793-9711

were: 5 1/2" at 4597' PBT 4597.5' Perfs at 4530-4540'

1st plug sand back to 4480' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls

release 8 5/8" rubber plug and pump 150 sx cement.

STATE CORPORATION COMMISSION

JUN 23 1986
6-23-86

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:00 am Day: 1 Month: May Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4480' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 700 psi and shut in 500 psi

Remarks: Recovered 2547.75' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED (if not) observe this plugging.

Signed Steve Durrant
(TECHNICIAN)

DATE JUN 23 1986
INV. NO. 14195