

2-21-88

141R

1 051010

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,215-0000
C SW SE, SEC. 17, T 16 S, R 26 W/E
660 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4981

Lease Name Carlson, Harold Well # A-1

Operator: Cholla Resources Inc.
Name & Address P.O. Box 1428
Golden, CO 80402-1428

County Ness 149.50
Well Total Depth 4600 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 216

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241

Address Box 819, Russell, KS 67665

Company to plug at: Hour: 6 p.m. Day: 21 Month: 2 Year: 19 88

Plugging proposal received from Bill Owens

(company name) Emphasis Oil Operations (phone) 913-483-3518
Elevation 2620'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2051-89'
1st plug at 2180' with 50 sx cement, 2nd plug at 1180' with 80 sx cement,
3rd plug at 240' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:15 p.m. Day: 21 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 2180' with 50 sx cement,
2nd plug at 1180' with 80 sx cement,
3rd plug at 240' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

2-24-88

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
to observe this plugging.

DATE 2-26-88

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 19913

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

CORRECTED INTENT

Expected Spud Date... January 31, 1988
month day year

API Number 15- 135-23,215-0000 East
... C SW SE Sec. 17. Twp. 16S S. Rg. 26... West
..... 660..... Ft. from South Line of Section
..... 1980..... Ft. from East Line of Section

OPERATOR: License # 4981
Name Cholla Resources Inc.
Address P.O. Box 1428
City/State/Zip Golden, Colorado 80402-1428
Contact Person William Goff
Phone (303) 526-1425

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 660..... feet
County Ness
Lease Name Carlson, Harold Well # A-1

CONTRACTOR: License # 8241
Name Emphasis Oil Operations
City/State Russell, Kansas 67665

Ground surface elevation 2620..... feet MSL
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Storage Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to bottom of fresh water... 180'
Depth to bottom of usable water... 1200' Kch.....

If OWWO: old well info as follows:
Operator
Well Name
Comp Date..... Old Total Depth.....

Surface pipe by Alternate: 1 2 X
Surface pipe planned to be set 200'
Conductor pipe required N/A
Projected Total Depth .. 4600..... feet
Formation Mississippian

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 2/3/88..... Signature of Operator or Agent [Signature] Title Agent

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X 2
This Authorization Expires 7-29-88..... Approved By [Signature] 2-4-88

Bill Owen * WAS: Surface Pipe: 350'
Spud - 9⁰⁰ PM - 2-12-88 -

ORIB. RCVD 1-29-88
(NO OWO)

PUSHER Bill Owen
TD 4600 FORMATION Missi
SURFACE PIPE 8 5/8 @ 216
ANHYDRITE 2051-89 ELEVATION 2620
STARTING TIME & DATE 6:00p 2-21-88
COMPLETION TIME & DATE 8:15p 2-21-88
1st PLUG @ 2180 FT. WI 50 SX
2nd PLUG @ 1180 FT. WI 80 SX
3rd PLUG @ 240 FT. WI 40 SX
4th PLUG @ 40 FT. WI 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY Allied
TECHNICIAN R.L.
60/40 @ 9/961

RECEIVED
FEB 24 1988
OIL AND GAS DIVISION
KANSAS