

1 030509

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,879-0000
SE NW, SEC. 17, T 16 S, R 26 W/E
3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7388

Lease Name Zenith Carlson Well # 1

Operator: Wichita Industries, Inc.
Name & Address 1801 California, Suite 4500
Denver, CO 80202

County Nesse 162.68

Well Total Depth 4648 Mississippi feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 364'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor R & C Drilling Co., Inc. License Number 9087

Address P. O. Box 296, Hays, KS 67601

Company to plug at: Hour: 12:00 am Day: 8 Month: September Year: 1985

Plugging proposal received from John Wise

(company name) R & C Drilling (phone) 913-625-4548

where: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2062-2097' Elevation 2643'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 50' below the base of the Cheyenne with 80 sx cement

3rd plug 30' out of the base of the surface pipe with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:00 am Day: 8 Month: September Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement, 2nd plug at 1180' with 80

sx cement, 3rd plug at 400' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with

10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED

SEP 17 1985

DATE _____

INV. NO. 10102

RECEIVED

STATE CORPORATION COMMISSION

Signed Steve Durrant
(TECHNICIAN)

SEP 16 1985
9-16-85
CONSERVATION DIVISION
Wichita, Kansas