

To: 1 050651
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,840 - 0700
C SW, SEC. 17, T 16 S, R 26 W/E
1320 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7388

Lease Name Carlson Well # A-1

Operator: Wichita Industries, Inc.
Name & Address 1801 California, Suite 4500
Denver, CO 80202

County Ness
Well Total Depth 4650 151.13 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 361

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Cheyenne Well Service License Number 6454

Address P. O. Box 916, Garden City, KS 67846

Company to plug at: Hour: 5:00 pm Day: 29 Month: October Year: 19 85

Plugging proposal received from Bill Dacon

(company name) Wichita Industries (phone) 303-293-8167

were: 5 1/2" at 4504' Perfs at 4522-34'; 4538-45' Pump through 2 3/8" tubing 5 1/2" using gel spacer between plugs

- 1st plug at 4100' with 25 sx cement
- 2nd plug at 2100' with 50 sx cement
- 3rd plug at 1200' with 50 sx cement
- 4th plug at 600' - cement to surface

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 6:30 pm Day: 29 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 4100' with 25 sx cement, 2nd plug at 2100' with 50 sx cement, 3rd plug at 1200' with 50 sx cement, 4th plug at 600' to surface with cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No recovery. DU tool ^{2100'} ^{4' cement to surface.} _{OS' 2}
(if additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

INVOICED

STATE CORPORATION COMMISSION Signed Richard W. Lacey (TECHNICIAN)

DATE NOV 4 1985

NOV 11-1-85 NOV 16 1985 JAN 16 1986

INV. NO. 10896 10-29