

1050048

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- <sup>135-</sup> 22,364 ~~0000~~

NW NW SW, Sec. 17, T 16 S, R 26 W1/2

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Carlson Well # 1

Operator: Chief Drilling Company  
Name & Address: Suite 905  
Century Plaza  
Wichita Kansas

County Ness

Well Total Depth 4600 feet 149.50

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 329

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347 Chase, Kansas 67524

Company to plug at: Hour: 9:00 am Day: 1 Month: November Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Mike Gomez

(company name) Kelso Casing Pulling (phone) \_\_\_\_\_

were: 1st plug off bottom with sand to 4200' + dump  
4sx cement. Then squeeze down 8 5/8"  
surface with 2sx hulls - 31sx gel - 100sx cement  
8sx gel - 8 5/8 wiper plug + 70sx cement. Using  
50/50 pozmix 6% gel 3% cc

Signed Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 am Day: 1 Month: November Year: 1983

ACTUAL PLUGGING REPORT Plugged as proposed in above paragraph  
Allied pumped the cement  
Recovered 2500' of 4 1/2 production pipe

Mr Earl Goodrow gave plugging orders +  
witnessed the plugging, because the company

Remarks: was plugging a well in gove county across  
the line

I hereby certify that the above plugging instructions were given as herein stated  
and that I (~~did~~ / did not) observe this plugging.

INVOICED  
DATE 11-21-83 NOV 7 1983  
INV. NO. 6094-W CONSERVATION DIVISION  
Wichita, Kansas

Signed Richard W. Lacey  
(TECHNICIAN)