

1 070006

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-135-22,145-0000
SW SW NW, SEC. 17, T. 16 S, R. 26 W/E
2970 feet from S section line
4950 feet from E section line

1-5

TECHNICIAN'S PLUGGING REPORT

Operator License # 5141

Lease Name Carlson Well # 1

Operator: Zenith Drilling Corporation

County Ness

Name:

Address 1861 N. Rock Road

Well Total Depth 4630 150.48 feet

Wichita, KS 67206

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 8:30 a.m. Day: 5 Month: 1 Year: 19 96

Plugging proposal received from David

(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

were: 4 1/2" at 4608' w/175 sx cement, Perfs at 4533-48'

1st plug sand back to 50' above perfs and dump 4 sx cement on top of sand through bailer,

2nd plug at 2000' with 50 sx cement. 3rd plug at 1200' with 80 sx cement,

4th plug at 600' with 40 sx cement, 5th plug at 360' with 40 sx cement,

6th plug at 40' with 10 sx cement.

Plugging Proposal Received by Bill Johnson
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 2 p.m. Day: 5 Month: 1 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4480' and dumped 4 sx cement on top of sand through bailer. All plugs displaced with gel,

2nd plug at 1900' with 50 sx cement. Pipe hung up, shot again at 1600',

3rd plug at 1200' with 80 sx cement,

4th plug at 600' with 40 sx cement,

5th plug at 360' with 40 sx cement, 6th plug at 40' with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 09 1996
1-9-96

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2000' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE JAN 23 1996
INV. NO. 44705
Observe this plugging.

Signed [Signature]
(TECHNICIAN)