

1 051910.

3-21

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 135-23,862-0000  
250' S of  
NE NE SE, SEC. 10, T 16 S, R 26 W/E  
2060 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4243  
Operator: Cross Bar Petroleum, Inc.  
Name & Address: 151 N. Main, Ste. 630  
Wichita, KS 67202-1407

Lease Name Baker Well # 1-10  
County Ness 148.53  
Well Total Depth 4570 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 355

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address: RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 7:30 a.m. Day: 21 Month: 3 Year: 1995

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2035-80' Elevation 2605' KB

1st plug at 2080' with 50 sx cement,

2nd plug at 1300' with 80 sx cement, 3rd plug at 700' with 40 sx cement,

4th plug at 380' with 50 sx cement, 5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 10 a.m. Day: 21 Month: 3 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 2080' with 50 sx cement,

2nd plug at 1300' with 80 sx cement,

3rd plug at 700' with 40 sx cement,

4th plug at 380' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE MAR 30 1995

INV. NO. 42483

Signed Richard W. Lacey (TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 24 1995  
4-24-95  
CONSERVATION DIVISION  
WICHITA, KS

EFFECTIVE DATE: 3-6-95

State of Kansas

135-23,862-~~0000~~

FORM MUST BE SIGNED

DISTRICT # 1

NOTICE OF INTENTION TO DRILL

ALL BLANKS MUST BE FILLED

SGA? Yes  No

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date March 8, 1995  
month day year

Spot 250' S. of East  
NE NE SE Sec 10 Twp 16 S, Rg 26  West

OPERATOR: License # 4243  
Name: Cross Bar Petroleum, Inc.  
Address: 151 N. Main, Suite 630  
City/State/Zip: Wichita, KS 67202-1407  
Contact Person: C. K. Morrison  
Phone: (316) 265-2279

2060 feet from South ~~North~~ line of Section  
330 feet from East ~~West~~ line of Section  
IS SECTION  REGULAR  IRREGULAR?

CONTRACTOR: License # 6039  
Name: L. D. Drilling, Inc.

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Ness  
Lease Name: Baker Well #: 1-10  
Field Name: Unice NE  
Is this a Prorated/Spaced Field? .... yes  no

Well Drilled For: Well Class: Type Equipment:  
 Oil ... Enh Rec ... Infield  Mud Rotary  
... Gas ... Storage  Pool Ext. ... Air Rotary  
... OWO ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes ... Other  
If OWO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Target Formation(s): Mississippian  
Nearest lease or unit boundary: 330'  
Ground Surface Elevation: 2614 feet MSL  
Water well within one-quarter mile: .... yes  no  
Public water supply well within one mile: .... yes  no  
Depth to bottom of fresh water: 800' 320'  
Depth to bottom of usable water: 1160' 1280'  
Surface Pipe by Alternate: .... 1  2  
Length of Surface Pipe Planned to be set: 350'  
Length of Conductor pipe required: None  
Projected Total Depth: 4550'  
Formation at Total Depth: Mississippian  
Water Source for Drilling Operations:  well  farm pond  other

Directional, Deviated or Horizontal wellbore? .... yes  no  
If yes, true vertical depth: \_\_\_\_\_  
Bottom Hole Location: \_\_\_\_\_

Will Cores Be Taken? .... yes  no  
If yes, proposed zone: \_\_\_\_\_

Exp. 9/1/95

AFFIDAVIT

340' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
It is agreed that the following minimum requirements will be met:



MAR 24 1995

Pusher Greg SPUD DATE 3-13-1995 INIT. GB  
 LENGTH SURFACE PLANNED 350'  
 RESERVE PIT STATUS- REMOVE FLUID LINED  
 after salt sect. bbls. when done bbls.  
 RATHOLED AHEAD? Y N SIZE HOLE  
 SURFACE PIPE 2 7/8 @ 355 CONDUCTOR  
 ANHYDRITE T- 2035 B-2050 ELEVATION 2605  
 TD 4570 FORMATION \_\_\_\_\_  
 RAN PIPE @ \_\_\_\_\_ DV TOOL \_\_\_\_\_ ALT II DONE \_\_\_\_\_  
 \_\_\_\_\_ SX \_\_\_\_\_ SX Y N  
 \_\_\_\_\_ Arbuckle Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
 \_\_\_\_\_ Hug./Council @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
 \_\_\_\_\_ Anhydrite Base @ 2050 Ft. W/ 50 SX  
 \_\_\_\_\_ 1/2 Base Anhy. @ 1300 Ft. W/ 80 SX  
 \_\_\_\_\_ 1/2, 1/2 Plug @ 700 Ft. W/ 40 SX  
 \_\_\_\_\_ Bottom Surface @ 2380 Ft. W/ 50 SX  
 \_\_\_\_\_ 40' Plug @ 40 Ft. W/ 10 SX  
 RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ \_\_\_\_\_ SX  
 WATER WELL \_\_\_\_\_ SX (Irr. Well \_\_\_\_\_ Pond \_\_\_\_\_)  
 TECHNICIAN R-L DATE 3-17-95  
 TYPE OF CEMENT 60/40 6% 1/4 Flowbeat  
 STARTING TIME 7:30 (AM/PM) DATE \_\_\_\_\_  
 COMPLETION TIME 10: (AM/PM) DATE 3-21  
 CEMENT COMPANY Allied