

15-077-00289-00-00

WELL PLUGGING RECORD

All information Completely
Required Affidavit
For Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Harper County, Sec. 8 Twp. 31 Rge. (E) 7 (W)

Location as "NE/CNW/SE" or footage from lines NW NW SE

Lease Owner Time Petroleum Company

Lease Name Richardson Well No. 1

Office Address 815 Union National Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 10 19 63

Application for plugging filed December 10 19 63

Application for plugging approved December 10 19 63


Plugging commenced December 10 19 63

Plugging completed December 10 19 63

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Archie V. Elving, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4831 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	250'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged as follows: Plugged at 275' with 20 sacks of cement and 1/2 sack of hulls and mud to 40'; plugged with 8 sacks of cement and 1/2 sack of hulls. Plugged rat hole with 2 sacks of cement and also put 2 sacks of cement in the mouse hole. Job completed at 5:00 A. M. December 10, 1963.

RECEIVED
STATE CORPORATION COMMISSION

DEC 11 1963
12-11-1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Charles W. Steincamp (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp
P. O. Box 355, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of December, 1963

My commission expires December 14, 1965

Elaine H. Taylor Notary Public.

INVOICED

DATE 12/12/63

INV. NO. 8273-W

15-017-00289-00-00

DRILLERS LOG

#1 Richardson

CASING RECORD:
242.22' of 8-5/8"
surface casing

COMPANY: Time Petroleum Company
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: NW NW SE
Section 8-31-7W
Harper County, Kansas

TOTAL DEPTH
4831'

COMMENCED: November 28, 1963

COMPLETED: December 10, 1963

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	106	Ran 242.22' of used 8-5/8" surface casing; set and cemented at 250' with 200 sacks common cement, 2% gel and 3% C. C.. Plug down at 8:00 P. M. 11-28-63. Cement circ..
Shale	106	460	
Red Bed, Shale & Shells	460	1245	
Shale & Shells	1245	1580	
Shale & Lime	1580	3875	
Lime	3875	4113	
Lime & Shale	4113	4375	
Shale	4375	4410	
Chat & Chert	4410	4580	
Lime & Chert	4580	4624	
Lime & Shale (Chalky)	4624	4710	
Shale	4710	4765	
Lime	4765	4781	
Lime & Chert	4781	4831	
Total Depth	4831'		

Ran two drill stem tests.

Ran Electra log.

RECEIVED
STATE CORPORATION COMMISSION

DEC 11 1963
12-11-1963
CONSERVATION DIVISION
Wichita, Kansas

D. & A.

Plugged hole as follows: Plugged at 275' with 20 sacks of cement and 1/2 sack of hulls and mud to 40'; plugged with 8 sacks of cement and 1/2 sack of hulls. Plugged rat hole with 2 sacks of cement and also put 2 sacks of cement in the mouse hole. Job completed at 5:00 A. M. 12-10-63.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 10th day of December, 1963.

Elaine H. Taylor
Elaine H. Taylor, Notary Public

My Commission Expires:
December 14, 1965