


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Harper County, Sec. 8 Twp. 31S Rge. (E) 7 (W)

Location as "NE/CNWKSWK" or footage from lines C SW NW
Lease Owner Pickrell Drilling Company
Lease Name Rutledge "A" Well No. 1
Office Address 705 4th National Bank Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 22, 1966
Application for plugging filed May 22, 1966
Application for plugging approved May 22, 1966
Plugging commenced May 22, 1966
Plugging completed May 22, 1966
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation Depth to top Bottom Total Depth of Well 4827 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	204'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 200'. Set plug. Cemented with
25 sacks cement. Heavy mud to 40'. Set plug.
Cemented with 10 sacks cement to bottom of
cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
06-02-1966
JUN - 2 1966

(If additional description is necessary, use BACK of this sheet)

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th National Bank Bldg. Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

C. W. SEBITS (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebits,
705 4th National Bank Bldg. Wichita, Kansas
(Address)

Subscribed AND Sworn to before me this 31st day of May, 1966



My commission expires May 10, 1970

L. M. Whiting, Notary Public.

15-077-30092-00-00

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th Natl Bank Bldg.
Wichita, Kansas

Rotary Drilling Commenced 5-9-66
Rotary Drilling Completed 5-22-66

LOCATION: Rutledge "A" No. 1, C SW NW Section 8-31S-7W, Harper County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: (8 jts) 8 5/8" surface casing set at 204', cemented with 170 sacks cement. Circulated. Completed 5:50 P.M. May 9, 1966. No oil string run, D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

115	Sand	C. F. S.
204	Red Rock	3933
1100	Red Bed & Shale	4000
3255	Shale & Lime	4040
3557	Sandy Lime & Shale	4078
3720	Lime, Shale & Sand	4415
3933	Shale & Lime	4425
3975	Lime	4774
4020	Lime & Shale	4778
4145	Lime	4782
4484	Shale & Lime	4790
4405	Shale	4794
4490	Mississippian	4800
4080	Miss Chert	4806
4605	Lime & Chert	4827
4630	Mississippian	
4774	Shale & Lime	Slope Test
4790	Lime	3000
4794	Viola	3500
4815	Sand	4000
4827	R. T. D.	4500

S. L. M.

3862

4137

4494

RECEIVED
STATE CORPORATION COMMISSION

JUN - 2 1966

06-02-1966

CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By: [Signature]
C. W. Sebits, Attorney-in-Fact

STATE OF KANSAS }
COUNTY } ss.:

May 10, 1966, before me the undersigned, a Notary Public, in and for the County of Harper, Kansas, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact. He acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

My commission expires May 10, 1970

[Signature]
L. M. Whiting, Notary Public