

API NUMBER 15-135-22,759-0601

LEASE NAME Deighton

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1-8

SW NE SE  
1650 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 8 TWP. 16S RGE. 26 XX or (W)

COUNTY Ness

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P.O. Box 947 Pratt, KS 67124

PHONE # (316) 672-7514 OPERATORS LICENSE NO. 5087

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 08-04-89 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Ft. Scott Depth to Top 4440 Bottom 4443 T.D. 4600

Lansing 'J' 4164 4169

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing 'J'	Oil	4158	4181	8 5/8	346	None
Ft. Scott	Oil	4438	4463	4 1/2	4596	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pressure tested 4 1/2" x 8 5/8" annulus to 1500 psi, could not pump in. Tied on to 4 1/2" csg. and pumped 400 lbs. hulls followed by 150 sxs of econolite cement. Final pressure vacuum. Waited on cement 48 hrs, ran wire line - top of cement at 1120'. Dumped 3.7 cubic yards of readymix cement to fill from 1120' to surface. Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Texas Energies, Inc. License No. 5087

Address P.O. Box 947 Pratt, KS 67124


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Texas Energies, Inc.

STATE OF Kansas COUNTY OF Pratt, ss.

Mark P. Stevenson (Employee of Operator) or ~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mark P. Stevenson

(Address) P.O. Box 947 Pratt, KS 67124



AND SWORN TO before me this 29th day of August, 19 89

Julia Berry  
Notary Public

My Commission Expires: Feb. 6, 1993