

15135-22093-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Ness SEC. 8 TWP. 16S RGE. 26W E/W  
 Location as in quarters or footage from lines:  
 SW NW NE


Lease Owner K & E Petroleum, Inc.  
 Lease Name SCHRATER Well No. 1  
 Office Address 300 Hardage Center, 100 S. Main, Wichita, KS 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed 10/21/81  
 Application for plugging filed 10/21/81  
 Plugging commenced 10/21/81  
 Plugging completed 10/21/81  
 Reason for abandonment of well or producing formation No commercial quantity of oil or gas encountered.  
 Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? YES

Locate Well  
 correctly on above  
 Section Platt.

Name of Conservation Agent who supervised plugging of this well Marion Schmidt  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4627'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set 1st plug @ 1260' with 70 sx.  
 Set 2nd plug @ 360' with 40 sx.  
 Set 3rd plug @ 40' Solid Bridge with 10 sx.  
 5 sx. in Rathole., 50-50 posmix, 4% gel, 3% c.c.

Plug was down @ 9:30 p.m., 10/21/81.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Jack L. Partridge, Vice Pres. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, KS 67202  
 (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of October, 19 81

My Commission expires: 7-13-85

Elizabeth G. Terry  
 Elizabeth G. Terry, Notary Public  
 STATE CORPORATION COMMISSION  
 RECEIVED  
 OCT 29 1981  
 10-29-81  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 NOTARY PUBLIC  
 STATE OF KANSAS

CONTRACTORS WELL LOG

15-135-22693-0000

OPERATOR: K & E Petroleum, Inc.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: SCHRATER #1  
 LOCATION: SW NW NE, Sec. 8-16S-26W  
 Ness County, Kansas  
 SPUD DATE: 10/12/81  
 COMPLETION DATE: 10/21/81

0	370	Surface Clay, Sand & Shale
370	2041	Sand & Shale
2041	2087	Anhydrite
2087	2276	Shale & Red Beds
2276	2490	Sand & Shale
2490	4627	Shale & Lime
	4627	Rotary Total Depth

Spud hole @ 4:00 p.m., 10/12/81. Drilled 369' of a 12 1/4" hole. Ran 9 jts. of 8 5/8" 20# casing set @ 367' and cemented with 225 sx. Common 2% gel, 3% c.c. Plug was down @ 9:20 p.m., 10/12/81. Cement did circulate.

4627' TD. Set 1st plug @ 1260' with 70 sx. Set 2nd plug @ 360' with 40 sx. Set 3rd plug @ 40' Solid Bridge with 10 sx. 5 sx. in Rathole. 50-50 posmix, 4% gel, 3% c.c. State plugger Marion Schmidt. Plug was down @ 9:30 p.m., 10/21/81.

SAMPLE TOPS:

Anhydrite 2041'  
 B/Anhydrite 2078'

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the SCHRATER #1, SW NW NE, Sec. 8-16S-26W, Ness County, Kansas.

ABERCROMBIE DRILLING, INC.  
**RECEIVED**  
 STATE CORPORATION COMMISSION  
 BY: *Jack L. Partridge*  
 Jack L. Partridge, Vice President

OCT 29 1981

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 23rd day of October, 1981.

CONSERVATION DIVISION  
 Wichita, Kansas

*Elizabeth G. Terry*  
 Elizabeth G. Terry  
 NOTARY PUBLIC

my commission expires 7-13-85

