


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

15-135-21364-0000

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202



Locate well correctly on above  
Section Plot

Ness County, Sec. 8 Twp. 16S Rge. 26W E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
SW NW SE

Lease Owner Beren Corporation  
Lease Name Dighton Well No. 1  
Office Address 970 Fourth Financial Center, Wichita, Kansas  
Character of Well (Completed as Oil, Gas or Dry Hole)  
dry hole

Date Well completed October 13, 1977 19  
Application for plugging filed October 13, 1977 19  
Application for plugging approved October 13, 1977 19  
Plugging commenced October 13, 1977 19  
Plugging completed October 14, 1977 19  
Reason for abandonment of well or producing formation  
dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Baltzor  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set. Hole plugged with 50-50 pozmix, 6% gel, as follows:  
70 sacks @ 800', 20 sacks @ 300', 10 sacks @ 40'.  
Plug down 12:00 a.m., October 14, 1977.

RECEIVED  
STATE CORPORATION COMMISSION  
11-4-77  
NOV 0 4 1977

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_

STATE OF KANSAS COUNTY OF BARTON, ss.  
Kenneth J. Link (employee of owner) or (owner or operator)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link President  
Box 355, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of October, 1977.

Loneita Barry  
Loneita Barry Notary Public.

My commission expires 3-28-80



DRILLERS LOG

15-135-21364-0000

Dighton #1

CASING RECORD:  
8 jts. used 8-5/8"  
surface casing

COMPANY: Beren Corporation  
CONTRACTOR: Strata Drilling Company

DESCRIPTION: SW NW SE  
Section 8-16S-26W  
Ness County, Kansas

TOTAL ROTARY  
DEPTH: 4580'

COMMENCED: October 6, 1977  
COMPLETED: October 14, 1977

ELEVATION: 2649' KB

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil, sand shale	0	342	Ran 8 jts. used 8-5/8" surface casing, set and cemented at 336' with 200 sacks common cement, 2% gel, 3% C.C. Cement circulated. Plug down 12:00 a.m., October 7, 1977.
Shale and sand	342	1489	
Blaine	1489	1499	
Shale	1499	2062	
Anhydrite	2062	2096	
Shale with lime streaks	2096	2965	
Lime and shale	2965	4415	
Lime	4415	4580	Ran one drill stem test.

Ran one electric log.

Hole plugged with 50-50 pozmix as follows: 70 sacks @ 800', 20 sacks @ 300', 10 sacks @ 40'. Plug down 12:00 a.m., October 14, 1977.

RECEIVED  
STATE COMPLETION COMMISSION

NOV 04 1977

CONSERVATION DIVISION  
Ness County, Kansas

STATE OF KANSAS )  
                  ) ss  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

*Kenneth J. Link*  
Kenneth J. Link, President

Subscribed and sworn to before me this 20th day of October, 1977.

My commission expires 3-28-80.

*Loneita Barry*  
Loneita Barry, Notary Public

